


## Agenda

- Review of project and design objectives
- Treatment processes:
  - Primary sedimentation Activated Tricking Filter - Secondary sedimentation – disinfection
- Construction of WWTPs using nonconventional design approach for process structures and equipment – How is it going?

## **Review-Plants design**


- In 2005, CDM under contract with USAID designed several small WWTPs for communities in the Bekaa Valley in Lebanon to help <u>clean up the Latana River</u>.
- Primary design objectives:
  - Low energy inputs to keep operating cost down.
  - Simple to operate and maintain
  - Secondary level of treatment
- Seven plants were design
- Fall 2005 funding for two plants modified D/B approach:
  - Aitanit-Qaraoun WWTP 5,000m<sup>3</sup>/day (1.3 mgd)
  - El Fourzol WWTP 1,000m<sup>3</sup>/day (0.3 mgd)
- Summer 2009 USAID funded construction of 2 more plants





## **Summary of WWTP Design Criteria**


- Design flow, 132 l/d/c (35 gal/d/c)
- Raw WW characteristics 400 mg/l BOD5
- Secondary Treatment
- Minimize O&M (energy) costs
- Simple O&M, through familiar equipment and simple visible processes
- Future upgrade for N & P removal
- Robust processes and structures


	BOD <sub>5</sub> (mg/1)	TSS (mg/1)	Total N <sup>1</sup> (mg/l)	Total P <sup>1</sup> (mg/l)
Raw Wastewater Influent	400	350	85	15
Effluent Requirements (ELV)	25	60	30	10























## PC to Trickling Filter Pump Station













## **Activated Trickling Filters (ventilation)**









## **Final Clarifier**


- See how the river water looks in Feb.
- Telescoping valves withdrawing sludge from hopper, launder channels sludge to pump station sump

















# <section-header><section-header><list-item><list-item><list-item>


### **Current Status**

- Aitanit WWTP sewer flow was received on April 23, 2009
- Aitanit WWTP commissioned on May 5, 2009.
  First operation modern WWTPs in Lebanon
- El Fourzol WWTP sewer flow was received on August 3, 2009
- Ablah WWTP anticipated construction start date September 21, 2009
- Chmistar WWTP anticipated construction state date February 2010 – reduce for new site

## Preliminary feedback on "Simple to operate and maintain" objective


- Robust design: Process & structures
- Hopper bottom clarifier & Digester
- Flows will not necessary be there when needed
- Low O&M costs & Low Capital costs challenging to reconcile
  - Single hopper bottom vs. multi hopper bottom
  - Concrete tank vs. steel or FRP tanks
  - Locally made vs. imported products

## Projected O&M Costs – El Fourzol WWTP for 1,000m<sup>3</sup>/day (0.3 MGD) plant



## Feedback on Construction Project Management

- Subcontracting:
  - Bidding without BOQ
  - Level of experience/ technical capacity
- Hopper bottom tank construction
- TF Tower Construction
- Local manufacturing
- Schedule





## <text><section-header><text><text>